BRUHAT BENGALOORE MAHANARA PALIKE,YELAHANKA ZONE

BYATARAYANAPURA DIVISION

SCHEDULE-B (As Per Negotiated)

BBMP/2014-15/RD/WORK_INDENT16524

Improvements and asphalting to HMT layout main road and cross roads in Ward no 09 of Vidyaranyapura Sub Division

Sl. No.	Description	Item Code	Unit	Qty	Sanctioned Estimate		Rates Quoted Before Negotiation		Rates Quoted After Negotiation	
							B B UMESHA		B B UMESHA	
					Rate	Amount	Rate	Amount	Rate	Amount
1	Earth work excavation by manual means in ordinary soil involving	1	Cum	660.53	75.6	49936.068	75.6	49936.068	79.37	52427.88
2	Scarifying existing stone metal layer upto 75mm thick along with	2	Sqm	2571.5	82.94	213280.21	82.94	213280.21	87.08	223922.89
3	Providing, laying, spreading and compacting graded stone aggre	3	Cum	394.5	1438.6	567511.92	1500.0	591750	1510.34	595830.76
4	Cleaning the existing WBM road surface including removing of bi	4	Sqm	4850	12.2	59170	12.2	59170	12.81	62122.58
5	Providing and applying tack coat using 80/100 grade bitumen (VG	5	Sqm	4850	18.74	90889	18.74	90889	19.68	95424.36
6	KSRRB M500-18: Providing and laying semi dense bituminous co	6	Cum	130.95	11070	1449616.5	12000.0	1571400	11622.39	1521952.36
7	Lead for Disposal of Debris shall be payable at carriage rates by	7	Cum	594.47	73.57	43735.158	73.57	43735.1579	77.24	45917.54
	Total					**2474138.86**		**2620160.44**		**2597598.38**
							B B UMESHA		**B B UMESHA**	
							2620160.44	**-2474138.86**	**2597598.38**	**-2474138.86**
							146021.58	**5.90%**	**123459.53**	**4.99%**
							2474138.86		**2474138.86**	

Over Sanctioned Rates

The Lowest Rates Quoted by B B UMESHA, Contractor is 4.99% Above the Sanctioned Estimate rates is recommended for kind Approval.

25/02

Assistant Engineer
Byatarayanapura Division

Executive Engineer
Byatarayanapura Division

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/RD/WORK_INDENT16524

NEGOTIATION SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/08/2014-15, Date: 30.12.2014

Improvements and asphalting to HMT layout main road and cross roads in Ward no 09 of Vidyaranyapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Negotiation Tender Rates of B B UMESHA	
				In Figures	In Words
1	660.53	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	79.37	Seventy nine point- Three Seven only
2	2571.5	Scarifying existing stone metal layer upto 75mm thick along with their bituminous surface, picking up scarified materials and stacking of old serviceable materials with lead of 100m, sequential spreading of the salvaged aggregates with fresh aggregates on prepared base and consolidating as per water bound macadam specifications including cost of all labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	Sqm	87.08	Eighty Seven point- zero Eight- only
3	394.5	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work	Cum	1510.34	one thousand five hundred & ten point- three four only
4	4850	Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	12.81	Twelve point Eight one only
5	4850	Providing and applying tack coat using 80/100 grade bitumen (VG10) on the prepared black topped surfaces at 2.5kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding clearing of road surface) including cost of all materials, labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work	Sqm	19.68	Nineteen point- Six Eight only
6	130.95	KSRRB M500-18: Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 508 complete in all respects as per specifications. using 100-120 TPH capacity H.M.P with sensor paver grading II (25-30mm) with 5% CRMB-55 grade, etc complete as per specifications and directions of engineer in charge of the work	Cum	11,622.39	Eleven Thousand Six hundred and twenty two point- Three Nine only

Sl. No.	Approved Qty.	Description	Unit	Negotiation Tender Rates of B B UMESHA	
				In Figures	In Words
7	594.47	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km etc complete as per specifications and directions of engineer in charge of the work	Cum	77.24	Seventy Seven point two four only

B. B. U

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

ಯಲಹಂಕ ವಲಯ ಬೆಂಗಳೂರು–92.

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ ಕಛೇರಿ
ಬೃ.ಬೆ.ಮ.ಪಾ. ಬೆಂಗಳೂರು–92.

ದೂರವಾಣಿ: 23636671

ಸಂಖ್ಯೆ: ಬೃ.ಬೆ.ಮ.ಪಾ/ಬ್ಯಾ.ವಿ/ಕಾ.ಅ/T-08 /2014–15 ದಿನಾಂಕ: 06/02/2015

16524

ರವರಿಗೆ,

Sri. B.B Umesh
Contractor, #385,
Bettaulsur (P),
Bangalore North Taluk-562157.

ಮಾನ್ಯರೇ,

ನೀವು ಟೆಂಡರ್ ಸಂಖ್ಯೆ: 08/14–15 ದಿನಾಂಕ: 30.12.2014 ರ ಇಂಡೆಂಟ್ ಸಂಖ್ಯೆ: 16524 ರಲ್ಲಿ ಭಾಗವಹಿಸಿದ್ದು, ಎಲ್–1 ಗುತ್ತಿಗೆದಾರರು ಹೊರಹೊಮ್ಮಿದ್ದು, ತಾವು ಟೆಂಡರ್ ಮೊತ್ತಕ್ಕಿಂತ ಹೆಚ್ಚಾಗಿ ನಮೂದಿಸಿರುತ್ತೀರಿ, ಆದ್ದರಿಂದ ನಿಮ್ಮನ್ನು ದರಸಂದಾನಕ್ಕೆ ಆಹ್ವಾನಿಸುತ್ತಾ, ಈ ಪತ್ರ ತಲುಪಿದ 3 ದಿನಗಳೊಳಗಾಗಿ ದರಸಂದಾನ ದರಗಳನ್ನು ಸಲ್ಲಿಸದಿದ್ದಲ್ಲಿ, ನಿಮ್ಮ ಟೆಂಡರ್‌ನ್ನು ರದ್ದುಪಡಿಸಿ ಮರುಟೆಂಡರ್ ಕರೆಯಲಾಗುವುದು ಈ ಬಗ್ಗೆ ಇನ್ನು ಮುಂದೆ ಯಾವುದೇ ತಿಳುವಳಿಕೆ ಪತ್ರಗಳನ್ನು ನೀಡುವುದಿಲ್ಲ.

ತಮ್ಮ ವಿಶ್ವಾಸಿ,

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, G.B.M.P.
Bangalore-92

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬಿಬಿಎಂಪಿ, ಬೆಂಗಳೂರು–92.

ರವರಿಗೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬಿಬಿಎಂಪಿ, ಬೆಂಗಳೂರು–92.

Date: 06/02/2015

ಮಾನ್ಯರೇ,

ವಿಷಯ:– ಧರಸಂದಾನ ನಡೆಸುವ ಬಗ್ಗೆ.
ಉಲ್ಲೇಖ:–ತಮ್ಮ ಪತ್ರ ಸಂಖ್ಯೆ ದಿನಾಂಕ:

****

ಮೇಲ್ಕಂಡ ವಿಷಯಕ್ಕೆಸಂಬಂದಿಸಿದಂತೆ, ಟೆಂಡರ್ ಸಂಖ್ಯೆ:08/14–15 ದಿ: 23.02.2015 ರ ಇಂಡೆಂಟ್ ಸಂಖ್ಯೆ ಕ್ಕೆ ನನ್ನ ಧರಗಳನ್ನು ನಮೂದಿಸಿ ನಿಯಮಾನುಸಾರ ಟೆಂಡರ್ ಸಲ್ಲಿಸುರುತ್ತೇನೆ ಉಲ್ಲೇಖ ಪತ್ರದಲ್ಲಿ ಧರಸಂದಾನ ನಡೆಸಲು ಕೋರಲಾಗಿದ್ದು, ಸದರಿ ಕಾಮಗಾರಿಯು ಡಾಂಬರೀಕರಣ ಕಾಮಗಾರಿಯಾಗಿದ್ದು ಮಾರುಕಟ್ಟೆಯಲ್ಲಿ ಸರಕುಗಳ ದರಗಳು ಹೆಚ್ಚಾಗಿರುವುದರಿಂದ ಶೇಕಡ +4.99% ಹೆಚ್ಚು ದರಗಳಿಗೆ ಕಾಮಗಾರಿ ನಿರ್ವಹಿಸಲು ಒಪ್ಪಿರುತ್ತೇನೆ.

ವಂದನೆಗಳೊಂದಿಗೆ

ತಮ್ಮ ವಿಶ್ವಾಸಿ